

CLIENT Boyd Smith  
SUBJECT 185 Massachusetts Avenue, Boston, MA

SHEET NO. \_\_\_\_\_

PROJECT NO. 151755.00

DATE 12/30/2015

BY PMM

CHECKED BY \_\_\_\_\_

Pricing for GFRC elements on East, South and West Elevations

	Description	Quantity		Unit Price	Total
1	Mobilization	1	ls	\$7,710.00	\$7,710.00
2	General Conditions	1	ls	\$14,150.00	\$14,150.00
3	Sidewalk Protection (east and south)	1	ls	\$27,560.00	\$27,560.00
4	Building access (Manlift, Swing, other)	1	ls	\$71,570.00	\$71,570.00
5	Remove/clean existing sealant from perimeter window frame-to-GFRC panel joints, GFRC-to-masonry joints and GFRC-to-GFRC wall joints	7,500	lf	\$8.20	\$61,500.00
6	Surface clean and preparation of GFRC surface (efflorescence)	6,000	sf	\$2.35	\$14,100.00
7	Two coats (min.) of KEIM Royalan exterior mineral silicate coating system (color to match existing GFRC panel system) *** Includes 2 coats	6,000	sf	\$5.60	\$33,600.00
8	Install new sealant at all joint locations (silicone sealant)	7,500	lf	\$6.90	\$51,750.00
9	Demobilization	1	ls	\$1,440.00	\$1,440.00
Total					\$283,380.00